APPENDIX C:




Phase 2: Project Concept/Identification **Phase Elements Site Examples**

Community

Visit potential project

Define project goal Identify action(s) needed to achieve goal



Improving channel

Phase 3: Feasibility

Project staff,

Landowners

scientists, stewards)

Phase Elements Identify stakeholders

- and resources Design project concepts
- Estimate costs for design and construction
- Confirm that objectives can be
- Evaluate potential project impacts


Who's Involved Site Examples Project lead staff (e.g. KC considered the Capital Improvement following questions:

- Will this project have an impact upstream or downstream or across stream properties?
- Will it impact the road?
- How will the channel respond to levee removal?

Capital Restoration Projects: from Conception to Construction

Using the Carlin Levee Project as an Example





Phase 4: Review Options and Make Selection

topographical and geotechnical surveys, create current conditions map, monitor groundwater)

- Assess real-life possibilities
- cost-effectiveness

Site Examples Protecting the road · Project lead staff (e.g. behind the levee was Capital Improvement a concern, so several scientists, stewards) solutions were considered: Landowners

- use a traditional riprap structure (e.g. put a lot of rock on the slope)
- use boulders combined with large woody debris at the base of the slope

· rely on the existing

Biologists

floodplain conditions

hydraulic modeling) · Complete 90% of project design

Phase Elements

Pre-construction

monitoring (e.g.

habitat surveys,

surveys, geotechnical

topographical

surveys, and

Phase 5: Design **Site Examples** Biologists Calculating the size of boulders and the Engineers distance between rock Geologists clusters was done to Landowner provide the needed






road protection.

Phase 6: Permitting

Conduct three to five individual and simultaneous permitting processes

Phase Elements

Local, state and federal agencies that protect and manage resources. (See back for complete




Eight permits were required for the following:

· Clearing and grading

Site Examples

- Dredging and filling Endangered Species Act (ESA) compliance
- Hydraulics approval
- Environmental protection
- Shoreline requirements
- Water Ouality Certification



File Name: 0507CIPdiagram. ai)

Phase 7: Final Design Site Examples

Phase Elements Incorporate changes from permitting

Finalize design

 Engineers Thumbnail of the levee , , , , CALL 2 WORKING DAYS REPORE YOU DIS 1600-424-5555 removal design

Phase 8: Construction

Phase Elements Begin construction

Schedule project

 Project lead staff Permitting staff within "fish window" Private contractor



Site Examples

Phase Elements • Actively monitor site for three to five years

Phase 9: Monitoring and Maintenance Site Examples

KC will be monitoring Project lead staff fish use at the project site. surveying the stream channel, and surveying the large

> Maintenance will include noxious weed removal and follow-up planting projects.

woody debris that was used.

King County

Department of Natural Resources and Parks **Water and Land Resources Division**

Ongoing maintenance

Project maintenance

SNOQUALMIE 2015 King County Page 75

APPENDIX C, CONTINUED





Capital Restoration Projects: From Conception to Construction

A Step-by-Step Look at a Complex Process





Phase 1:

Watershed-Level Planning

During Phase 1 of planning the lead agency identifies a primary goal that needs to be achieved (e.g. salmon recovery, flood reduction, watershed health issue, drainage issue) and then determines what must be done to achieve that goal (e.g. what type of projects or actions). To achieve salmon recovery, for example, Phase 1 analysis would determine the type of habitat that would provide the greatest increase in salmon productivity. During this phase, specific project information is limited. This phase is supported by the operating budget of the project lead and possibly support from other jurisdictions.

Timeline: about one to two years. Generally plans are relevant for ten years. Following that, updates should be made. **Cost:** determined by scope of issues and goals needing to be addressed.

Phase 2:

Project Concept/Identification

During this phase the general principles in Phase 1 are applied on a site specific basis. This phase requires significant familiarity with the natural resources of an area in an attempt to determine the best location for a project. Primary consideration is given to the benefit(s) the project will provide. Support for Phase 2 continues to come from an operating budget.

Timeline: emerging concepts should be considered on an ongoing basis with new priorities made annually. **Cost:** \$5,000 annually per concept.

Phase 3:

Feasibility

During the feasibility phase of project development, specialists (e.g. engineers, geologists, hydrologists, ecologists) begin analyzing the following questions:

- Can the project be constructed?
- Will the project achieve the benefits predicted in Phase 2?
- Will there be project impacts?
- Do the impacts prevent construction or require mitigation?

- Is there support for the action?
- What is the cost of the project?

The specific goal of this phase is to make a decision about whether or not a project should be pursued. Granting agencies want many of these issues resolved before allocating funds to the project.

Feasibility studies are funded through the project lead's operating budget and money earmarked for Capital Improvement Projects (CIP) as well as grant funds.

Timeline: six months. **Cost:** \$20,000 - \$150,000, depending on scale and existing data.

Phase 4:

Review Options and Make Selection

Once a project concept has passed the feasibility phase, there are usually a variety of actions that can be taken to accomplish the project objectives. The design team must choose a specific set of actions from the range of potential activities within the project concept. At this point, substantial financial investments in the project are required (e.g. surveys, geotechnical study, etc.). Funding for Phases 4 through 8 comes from CIP budget and grant money.

Timeline: three to six months. **Cost:** \$50,000 - \$300,000.

Phase 5:

Design

The design phase is the development of the actual project plans for the specific suite of actions selected in Phase 4. While cost or unforeseen circumstances can require the design team to revisit options considered in Phase 4, for the most part the focus is on the details of the proposed actions. For example:

- How many feet of the levee will be removed?
- How much large woody debris is needed to accomplish the desired function?
- What plants should be used and where?

This phase facilitates the funding process by making it clear what will actually be funded. Biologists and engineers take in feedback throughout Phases 1 through 4 and then design a project that will meet

the project team's ecological goals, landowner goals, and known permitting constraints. Design is only 90% complete to allow permitting agencies to make any needed adjustments.

Timeline: three months. Cost: \$25,000 - \$400,000.

Phase 6:

Permitting

Each project requires a variety of permits from local, state and federal agencies that protect and manage natural resources. Agencies typically involved are:

- WA Department of Fish and Wildlife
- WA Department of Natural Resources
- WA Department of Ecology
- King County Department of Development & Environmental Services
- US Fish & Wildlife Service (USFWS)
- National Oceanic & Atmospheric Administration (NOAA)
- Army Corps of Engineers

If the project is going to affect Chinook or bull trout, all the permitting agencies will consult with the NOAA, National Marine Fisheries Service, and USFWS to determine if there are any Endangered Species Act issues. Each permitting agency also has their list of requirements for which a project must be screened. Minor changes or conditions are commonly added to a project during the permitting phase.

Timeline: three months. **Cost:** \$25,000 - \$400,000.

Phase 7:

Final Design

The design is final at this phase and includes several elements. For example:

- a site map
- planting plan
- specific design element details (e.g. how deep to put large woody debris, what angle, etc.)
- required materials

Timeline: one to three months. Cost: \$5,000 - \$25,000.

Phase 8:

Construction

Construction usually includes upland (e.g. planting) and instream—work done in the water—elements. Instream work can only be done during specific times of the year based on when different fish species will not be present in the water during construction. This "fish window" ranges from two to three months, depending on the type of fish present. Permits, like clearing and grading, affect when upland activities can be done. Typical CIP in-stream construction is actually only done during a short period of time each year. Planting takes place between November and March.

Timeline: three to 15 months. **Cost:** \$200,000 - \$2 Million.

Phase 9.

Monitoring and Maintenance

Once a project is constructed there are several types of monitoring that are undertaken. The two that take place most often with CIPs are:

- Implementation monitoring—the process of determining if the planned activity occurred as planned.
 (Did we build what we said we would?)
- Direct effectiveness monitoring attempts to answer if the project is achieving the desired results or not and typically lasts between three and five years.

Maintenance issues are generally identified through site monitoring. Low native plant survival or invasive plant species coming in are two of the usual site maintenance activities that need to be done.

Funding for monitoring and maintenance comes from the project lead's CIP budget.

Timeline: three years+. Cost: \$15,000 - \$100.000.

File Name: 0507CIPdiagHandout.pdf



Department of Natural Resources and Parks
Water and Land Resources Division

Page 75 King County SNOQUALMIE 2015