CLIENT: KING COUNTY | PROJECT: N. CREEK DIVERSION

SUBJECT: CSO STORAGE AT NORTH CREEK P.S.

ADDITIONAL COST IF P.S. WAS DEEPENED TO ACCEPT GRAVITY FLOW FROM CSO STORAGE

ADDITIONAL DEWATERING:	LS	= 5,000
EXCAVATION:	2800 CY @ $8/CY	= 22,000
SHORING:	5000 SF @ $40/SF	= 200,000
CONC:	1000 CY @ $400/CY	= 400,000
	TOTAL	$627,000 ±

KCM	2485028-007	WG.	12/21/95	3
	JOB NO.	BY	DATE	SHEET NO.