



King County is in process of preparing a construction document for advertising in August 2006. The design is at 60% level.

Bidders and suppliers who are interested in finding information, may contact Shahrzad Namini at (206)296-1434 or [Shahrzad.namini@metrokc.gov](mailto:Shahrzad.namini@metrokc.gov).

The work of the new forcemain contract consists of:

1. Traffic control.
2. Restoration of temporary driveway areas and installation of fire protection piping at Brookside Office Park and SanMar Building.
3. Site preparation, erosion and sediment control, and noise mitigation construction.
4. Installation, maintenance, and monitoring of geotechnical instruments and monitoring points.
5. Installation of approximately 572 lineal feet of 24-inch diameter force main by open trench, approximately 4843 lineal feet of 24-inch carrier pipe and 30-inch steel casing pipe by horizontal directional drilling, and associated force main connection into the Wilburton Siphon.
6. Installation of vacuum valves, air relief valves, odor control canisters, and associated manholes and concrete vaults along the force main alignment.
7. Installation and dewatering of excavation support systems.
8. Restoration of construction staging areas and open-trench sections and all other surface and underground features damaged during the course of work.
9. Removal of obstruction in 16" siphon barrel of Wilburton Siphons and replacement of 16" pipe section.