Hidden Lake Pump Station and Sewer Improvement Project

Replace Part of the **Boeing Creek Trunk Sewer**

- Use current route
- Replace approximately 12,000 feet of sewer, including corroded pipe
- Improve odor control in problem areas

Construct a New Underground Storage Pipe

- Build a 500,000-gallon pipe in Boeing Creek Park
- Locate the pipe under and next to the City's existing stormwater facility
- Replace about 1,000 feet of pipe in street
- Coordinate construction with City's stormwater project
- Restore street and park after construction ends

Replace Hidden Lake **Pump Station**

- Use the existing site
- Increase the pumping capacity from 4.3 million gallons per day (mgd) to 6.8 mqd
- Design building and landscape to fit the community
- Select equipment to optimize system operation and reduce odors and noise



Project Component and Number Road •••• Richmond Beach Wastewater Service Area Overflow to Puget Sound Existing Sewer Line

Boeing Creek Trunk Sewer Line Replacement Area